

SITE WASTE MANAGEMENT PLAN

PROPOSED DWELLING Land east of No. 19 Elderberry Way, Coventry.

Planning Application Number P/2020/1486

INTRODUCTION:

This plan applies to all activities throughout the project when project value is below 2300k.

All Contractors and Subcontractors will be made aware of the requirements in this Site Waste Management Plan at contractor selection, pre contract start meetings, and the initial site Induction.

Contractor to ensure that

- A Site Waste Management Plan is set up for each project.
- That the following waste hierarchy is applied:
 1. Reduce
 2. Re-use
 - 3, Recycle
 - 4, Recover
 5. Dispose
- The waste is segregated (where possible and dependant on volumes produced), secured, labelled and collected safely and completed by any sub-contractor.
- That all waste for disposal is safely deposited at a licensed disposal / exempt / recovery facility. That any incidents of incompetence or mishandling or illegal disposal are reported.
- That Waste Transfer / Consignment Notes are correctly completed for each approved transfer.
- Verification of Waste Carrier Registration Certificates and Licences,
- The procedures detailed in this plan are brought to the notice of all employees and subcontractors and employees.

DEFINITIONS OF WASTE:

Waste is widely defined and includes excess unwanted materials, effluents; unwanted surplus substances arising from the application of any process and any substance or article which is broken, worn out, contaminated or otherwise damaged. Waste becomes controlled by legislation when it is discarded by the holder, Materials being returned to the company stores or supplier for credit are not to be considered as waste. Materials sold for re-use or re-cycling may still be classified as waste and subject to all statutory controls, including Duty of Care.

MONITORING:

The implementation of waste management procedures will be monitored through weekly site inspections and Health, Safety and Environmental Inspections and Audits in accordance with the Site Waste Management Plan will be reviewed at 3 monthly intervals.

REPORTING:

The Project Manager / Site Agent will be responsible for producing a Progress Report / Construction Site Quarterly Report as per client requirements.

RECORDING:

The Project Manager / Site Manager / Site Agent will keep up to date with this Site Waste Management Plan and ensure all Waste Transfer documentation, Registration Certificates and Disposal Licences / Exemptions with Environment Agency validation confirmations are filed in accordance with the standard site filing system.

Copies of all waste documentation will be retained for 3 years.